

Public (P. Audit) (1953) Department.

SERIES.

G.O. NO. MS. 749

Dated 20-3-1953.

Passed

By *22/3/53*

Superintendent

go or p. 3.

[Despatch Abstract.]

Community Projects - South Kanara Dt. -
Block I - Communications - Construction
of a foot-bridge across Pavanje stream
at Koluwail near Haleangady - Estimate -
Sanctioned.

Back Papers.

G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.

Further Papers


G.O.	No.	Department.	Date.	G.O.	No.	Department.	Date.
Lodges	19700	Public (C.P.)	2.7.53				
Lodges	3010	Public vi) / m	12/11/54				

From

Sri G. Simhadri, B.A.,
Project Executive Officer,
Mangalore.

To

The Director of Community Projects
and Ex-Officio Secretary to Govt.,
Fort St. George, Madras.



Sir,

.....

COMMUNITY PROJECTS - South Kanara Block I - Communications
Construction of a foot-bridge over Pavanje stream at Koluvaill
near Haleangady - Estimate - Sanction - Requested.

I submit herewith an estimate in duplicate with necessary
site plan etc., for the construction of a foot-bridge across Pavanje
stream at Koluvaill near Haleangady. The necessary particulars
relating to it are furnished below:

1. Block No. 1.
2. Name of work. Construction of a foot-bridge across Pavanje
river at Koluvaill near Haleangady.
3. Whether approved)
by the Firka and)
the Project Advisory)
Committees and included)
in the work programme)
for 1952-53.) Yes.
4. Value of estimate. Rs. 11,000/-
5. Contribution promised.)
1. The Haleangady Panchayat Board has
promised a contribution of Rs. 2,000/-
)
2. The contribution promised by the
villagers is Rs. 500/- and land required
on either side of the stream.
)
3. Total Rs. 2,500/- plus land required
on either side of the stream.
6. Expenditure to be)
borne by the Community)
Projects.) Rs. 8,500/-

7. Remarks: Koluvaill is an island in the Pavanje River. It is a
hamlet of Haleangady village. There are over 300 residents in
this locality. They have no school or market of their own and for
all such amenities they have to go to Haleangady bazaar after
crossing the stream. As there is no foot-bridge at present, they
cross the stream using boats. During the rainy season when the
stream is in floods, the inhabitants of the locality are completely
cut off from Haleangady for days on end. So, the construction of
a foot-bridge at the site proposed is an absolute necessity. The
site was inspected by the Director of Community Projects, Madras
when he visited this area last month. The estimate may be
sanctioned for Rs. 8,500/-

Sri R.B. Vaghaiwalla, I.C.S., Director, Community Projects
Administration has programmed to visit this area from 14-3-1953
to 16-3-1953. It is proposed to collect material necessary for
the construction of the work in the meanwhile to commence the
work on that day. I therefore request that the estimate may be
sanctioned and returned to me sufficiently early.

Enclosure

PROJECT EXECUTIVE OFFICER.

Estimate in duplicate

[C.N^o 4371/53]

G.O. MS. N^o 749

, dated 19/3/53.

Abstract: Community Projects - South Kanara Dist.
Block I - Communications - Construction
of a foot-bridge across Pavanje Stream
at Koluvail near Haleangady - Estimate -
Sanctioned -

Issue. M.

19/3/53

P. I. C.F.

Read: From the P.E.O., Mangalore, C.N^o 732/53-B
dated 2.3.53.

Order:

Sanction is accorded to an expenditure not exceeding Rs. 8500/- (Rupees eight thousand five hundred) only, out of the estimated cost of Rs. 11,000/-, for the construction of a foot-bridge across Pavanje Stream at Koluvail near Haleangady, Mangalore Taluk. The balance of the estimated cost required for the completion of the work, should be contributed by the Haleangady Panchayat Board and the villagers, as indicated in the P.E.O.'s letter read above. The P.E.O. will get the work executed and submit the completion report to Govt. in due course.

2. The expenditure is debitable to
"63-B. Community Development Projects -
II Community Projects - f. Communications,
(foot-bridges) -

3. The plan and the estimate approved for Rs. 11,000/- are herewith returned to the P.E.O., Mangalore.

To (By Registered Bdt)

The P.E.O., Mangalore 17/3/53
(with enclosures).

" A.C. Mr. ...

Copy to the P.E.O. Accounts ...

" " P.E.O. Technical ...

" " P.E.O. Admin. ...

S.F. ...

Ch. 3 ...

Note:

Please see the letter from the P.E.O., Mangalore

Entered in
Ch. 3


at P.I.C.F. The proposed foot-bridge is of timber, 163 ft long and 4'-6" wide, with hand-rails 3'-0" high on sides. The ~~platform~~^{decking} of the bridge is of 2" thick planking at an elevation of 2'-0" above the Maximum Flood Level of the stream, fixed to longitudinal beams resting on two parallel rows of piles (12" diameter) driven upto ~~about 20 ft depth~~^{about 20 ft depth} and stiffened by cross-braces. The end piles are proposed to be encased with rough stone dry packing pointed with cement mortar (1:4), and ~~the remaining piles~~^{the rest} painted with coal tar two coats applied hot with portion above the low tide level encased with wire netting and plastered over with cement mortar (1:4) 3/4" thick, for protection against the wearing action of ~~saline water~~^{saline water}. The rest of the structure (the beams, braces, ~~platform~~^{decking} of the bridge, hand-rails etc) is also proposed to be given two coats of coal tar applied hot to withstand the effects of exposure. The estimate has been scrutinised and is in order. The amount of contribution forthcoming is Rs 2500/. The estimate may, therefore, be sanctioned for (Rs 11,000/- minus Rs 2500/-) Rs 8500/- as requested by the P.E.O. Subject to orders, the draft order put up may be approved. The two copies of the estimate may also be signed -

kept below

f2/p2
17.3.53.

Please see A on p 1 of at
one estimate may be counterigned
D.S. may see after time.

for
18.3.53.

19.3.53 / 

by
24/3 +
D.S. (a.i.)

* Signed